

Pre-Installation Checklist

For Home Installations



1 Ensure HydroMassage® space is cleared and ready for delivery

NOTE: Carpet is recommended under the HydroMassage® unit to minimize sound during use.

2 Ensure the following are available:

- A. Distilled water must be used:
For Lounge models: 12 gallons/45 liters
For Bed models: 30 gallons/114 liters
- B. 220V / 30A outlet with NEMA L6-30 locking receptacle
- C. CAT5 internet connection recommended for technical support and automatic software updates (NOTE: Internet connection required)

3 Upon delivery, check to ensure no damage has occurred during shipping

- A. Shipping boxes
- B. Bed/Lounge side panels
- C. If any damage has occurred, please let the delivery driver know prior to leaving the premises. If possible take photos of the damage and contact the HydroMassage® support department at your earliest convenience.

4 Position HydroMassage® in desired location prior to adding water



CAUTION: If any changes to scheduled delivery/or install dates, please advise HydroMassage® Sales Support a minimum of 48hrs prior to scheduled dates.